3. The purchaser shall not sublet the harvesting of pasturage without previous sanction of the District Forest Officer. When such sanction is accorded, the sub-lessee will be bound by all the terms and conditions of the sale jointly and severally with the original purchaser. The purchaser shall furnish a list of men allowed to enter the plantations, etc., to cut and remove grass and shall hold himself responsible for breach of any of the Forest Rules and for the occurrence of fire in the plantations, etc., due either to himself or his men, which will be dealt with under the provisions of the Mysore Forest Regulation. He shall deposit a sum equivalent to 10 per cent of the purchase money for the due fulfilment of the lease and shall execute an agreement for that purpose.

4. The purchaser shall not scrape or dig the grass in the plantations, but shall only cut and remove it or graze it.

5. The grass crop in the plantations will be allowed to be cut and removed or grazed only between sunrise and sunset up to the end of the period stipulated, *viz.*, end of December 1932. No storage of grass will be allowed in them. Cattle will be allowed to graze in the plantations only between sunrise and sunset.

6. The purchaser shall not interfere with any forest operation such as planting, sowing and felling that the Forest Department may wish to conduct in the leased area. Should any damage be caused by such operations to the grass crop, he shall not be entitled to any compensation.

N.*B.*—The lessee will maintain the fencing, trench and other boundary marks in order.

7. Tree growth should not be injured or lopped.

8. In the event of a breach of any of the conditions specified in the sale notice or agreement, the lease will be liable to be cancelled, all the produce collected confiscated and a penalty not exceeding Rs. 25 levied and recovered as an arrear of land revenue by the District Forest Officer and the security deposit or part thereof forfeited.

C. H. EAGLES,
District Forest Officer.

ENGINEERING DEPARTMENT.

KOLAR DIVISION.

Dated 26th May 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 15th June 1932, for the work of restoring Kariyappanhalli Tank Regd. No. 635—382, Chintamani Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th June 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 175 in cash or Government Currency Notes, as earnest money and be superscribed "Tender for the work of restoring Kariyappanhalli Tank Regd. No. 635—382 of Chintamani Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned,

Abstract estimate for the probable cost of restoring Kariyappanhalli Tank Reg. No. 635—382, Chintamani Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	BUND.		Rs. a. p.		Rs.
1	Cutting grips to old bund	Grade	5 0 0	24	120
2	Earthwork to bund including lead and lift watering and tamping.	C.yd.	0 4 0	4,405	1,101
3	Puddle wall	,,	0 12 0	243	182
4	Turfing	S.yd.	0 1 0	4,652	290
5	New stone work	C.yd.	1 12 0	603	1,055
6	Resetting old stone with new jelly	,,	0 12 0	130	98
7	Fixing new grade stones chistling, figuring and painting, etc., complete.	Each	1 8 0	29	44
8	Fixing Index stone	,,	0 8 0	29	15
9	Do Reg No. stones	,,	3 0 0	1	3
10	Do gauge stone	,,	15 0 0	1	15
11	Do Date stone	,,	3 0 0	1	3
	Total ..	..	..	..	2,926
	SLUICES.				
1	Examining and repairing No. 1 and 2 sluices and providing plug and rod with locking arrangements.	Each	100 0 0	2	200
	WASTE WEIR.				
1	Earthwork excavation	C.yd.	0 4 0	67	17
2	Stone jelly in concrete	C.ft.	0 4 6	102	29
3	Burnt stone in surki	,,	0 5 0	153	48
4	Burnt stone slabs 6" thick	S.ft.	0 6 0	183	68
5	Cement pointing	Sqr.	4 0 0	2·5	10
6	Providing joggle joints	..	0 8 6	6	3
7	New stone work	..	1 12 0	17	30
8	Clearing draft and approaches	C.yd.	0 4 0	55	14
	Total ..	..	..	..	219
	Grand Total Bund, Sluice and Weir Rs. 2,926+200+219 ..	..	..	—	3,345

C. T. NARASIMHA IYENGAR,
Executive Engineer.

TUMKUR DIVISION.

Dated 25th May 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 3 P.M. of 20th June 1932, for opening out a road from Chiknaikanhalli to Mattighatta. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of December 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or currency notes as earnest money, and superscribed "Tender for opening out a road from Chiknaikanhalli to Mattighatta," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender of the successful competitor will be required to execute the usual bond, in default of which, his tender will be cancelled, and earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On receipt of one of the tenders, the earnest money on rejected tenders will be returned.

9. *Percentage rates above or below the estimated amount will not be accepted.*

10. No claims for enhanced rates will be entertained on any account after acceptance of tender.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates and measurements, quality of work, etc., and in all disputes of any kind the decision of the Superintending Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lumpsum provisions are subject to modification as per data worked out during execution. The individual item of work under lumpsum provisions the rates tendered for similar items of work, will be paid and for other items, the rates as per schedule of rates, will be paid at the discretion of the Executive Engineer.

Abstract estimate of quantities for opening out a road from Chiknaikanhalli to Mattighatta :—

Sl. No.	Details	Unit	Quantity	Rates in	
				Figures	Words
				Rs.	Rs.
	I. *Formation of Road.*				
1	Clearing jungle	Furlong	56		
2	Cutting date and other trees	L.S.			
3	Removing stray boulders	L.S.			
4	Earthwork excavation and using the spoil for formation.	C.yd.	18,569		
5	Forming road way with consolidation by stone road rollers.	Mile	10½		
6	Revetting slopes to tank bunds wherever necessary.	L.S.			
7	Providing stone finger posts with 3 arms as per design.	Each	2		
8	Providing zero and mile stones ($4\frac{1}{2} \times 1\frac{1}{4} \times \frac{1}{2}$) dressing, chiselling figures and painting and fixing complete as per design.	,,	11		
9	Do do furlong stones (size $2\frac{3}{4} \times 5/8 \times \frac{1}{2}$).	,,	74		
10	Providing land width stones ($3 \times \frac{1}{2} \times \frac{1}{2}$) including dressing to a height of 6 inches.	,,	338		
11	Excavating and stacking gravel for 4, 5/6 4/7, 1 and 2/8 with lead for 110 cyds. per furlong.	C.yd.	550		
12	Spreading, forming and consolidating gravel	,,	550		
13	Providing stone road rollers 3'-0" x 2½' diameter with iron frames.	,,	2		
	II. *Cross Drainage Works.*				
	(1) Constructing a tunnel of 2 vents 3' x 4' in 2/1 of the Road :—				
1	Earthwork excavation in gravelly soil ...	C.yd.	34		
2	Surki concrete	C.ft.	208		
3	Size stone in surki mortar	,,	964		
4	Rough stone apron with jelly wedging including 3 miles lead.	C.yd.	23		
5	Burnt stone slabs 6" thick dressed and fixed	S.ft.	257		
6	Pointing with surki mortar	Sqr.	3·42		
7	Providing wheel guard stones	Each	4		
	(2) Constructing an irrigation tunnel at 2/5. of the road.	L.S.			
	(3) Construction of rough stone causeways in different places-length of total causeways is 737 feet.	...	...		
1	Earthwork excavation in gravelly soil ...	C.yd.	...		
2	New rough stone work with jelly wedging and lead of 3 miles.	,,	...		
3	Burnt stone 6" thick dressed and fixed wheel track slabs.	S.ft.	...		
4	Easing gradients on either sides of causeway	L.S.			

A. TANDONI RAO,
Executive Engineer.

HASSAN DIVISION.

Dated 26th May 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 15th June 1932, for Restoring Akkalavadi Breached Tank, Registered No. 20 of Arkalgud Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 (Rupees one hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Akkalavadi Breached Tank Registered No. 20 of Arkalgud Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Abstract estimate for Restoring Akkalavadi Breached Minor Tank Registered No. 20 of Arkalgud Taluk.

Item No.	Particulars	Unit	Quantity
	Bund.		
1	Earthwork to bund	C.yds.	220
2	The quantity of earthwork to bund from breach site as per deduction.	,,	420
3	Breach filling with selected earth	,,	1,020
4	Puddle wall with clay including foundation	,,	142
5	Turfing to bund	S.yds.	1,914
6	Revetment to bund	C.yds.	120
7	Providing grade stones	No.	11
8	Do index	,,	11
9	Do B. M. Stones	,,	2
10	Do Guage	,,	1
11	Date and Register number stone	,,	1
	Constructing a Weir at R. L. 50·00.		
1	Earthwork excavation	C.yds.	270
2	Filling foundation with concrete in surki mortar ...	C.ft.	177
3	Burnt brick in surki mortar	,,	259
4	Plastering with surki mortar	S.qr.	3·86
5	Burnt stone slabs 6" thick for coping	S.ft.	162
6	Burnt stone work old	C.yds.	34
7	Do new	,,	33
8	Jelly backing behind revetment	,,	40
9	Gravel do	,,	30

M. A. SRINIVASACHARI,
Executive Engineer.